

ADDENDUM NO. 1

**PROJECT: Hickory Hills Snow Making Well**  
**PROPOSALS DUE: Monday, September 24, 2018, at 11:00 AM**

This addendum is issued prior to the receipt of proposals to amend the proposal as follows:

1. SPECIFICATIONS:

- a. The specifications provided are based on preliminary data and should be considered a minimum. The new well needs to be capable of delivering 500 GPM at 100 psi to the suction line of the existing booster station. We understand that a 40 HP pump may not meet these needs and have arranged to have the VFD controller capable of up to 60 HP for the well pump motor. If a larger than 8" casing and pump better fit and is more cost effective then please note on the bid form the casing size and pump motor, etc that is being provided.
- b. Piping between new well and booster pump suction line-The new well will be situated approximately 70' from the existing booster bump suction line. Provide a cost for installing 6", schedule 80 piping and connecting to a mechanical flange fitting in the space provided below:

**Total cost of up to 70 feet piping between new well and existing booster pump suction line:** \$ \_\_\_\_\_

All other conditions of this Request for Proposals remain the same.

Bidders must acknowledge receipt of this addendum. Acknowledgement must be shown in the spaces provided herein and must be received with the bid, **Monday, September 24, 2018, at 11:00 AM**, local time, at the place of bid opening at the **Office of the City Manager, Second floor, Governmental Center, 400 Boardman Avenue, Traverse City, Michigan, 49684**.

FAILURE TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM MAY CAUSE REJECTION OF BID.

Sincerely,



Timothy J. Lodge, P.E.  
City Engineer

Dated: \_\_\_\_\_

ACKNOWLEDGED:

Bidder: \_\_\_\_\_

By: \_\_\_\_\_

Title: \_\_\_\_\_