Grandview Parkway Letter of Understanding

CHRIS ZULL, PE – TRANSPORTATION PRACTICE LEADER, PROGRESSIVE AE

OUTLINE

Project Overview

• 5-2-22 Commission Feedback

• 1947 Agreement


Consequences of a Yes vote

What is the purpose of the LOU?

Successes


Consequences of a No vote

Schedule



PROJECT OVERVIEW

- US-31/M-37/M-72 (Grandview Parkway) from Division Street (US-31/M-37) to Garfield Avenue
- City of Traverse City, Grand Traverse County
- \$21.7M Programmed Investment



3-21-22 MDOT LETTER OF UNDERSTANDING

- MDOT to construct as coordinated through weekly project team meetings
 - Plan detail development continues
 - Design is substantially complete (95+%)
- Incorporate City water and sanitary sewer utility work as part of the project
- Coordinate grading and traffic detour permitting with Traverse City Engineering
- Incorporate signage to encourage the use of Garfield Avenue
- Increase left turn lane storage for EB Front at Garfield Avenue
- Look to program a future project for M-37 north of Front Street

SUCCESSES – TRAVERSE CITY

The design process proceeded with the mutual **intent to slow traffic** and improve infrastructure for all users resulting in benefits to the City in excess of \$1.15M. These successes include:

- 1. Geometric improvements at intersections to improve traffic safety, pedestrian and cyclists' mobility, and operations
- 2. Improvement of sidewalks, trails, and related non-motorized facilities within the project

a. Including intentional design consideration for future trail and lighting projects

- 3. Landscaping along the corridor including new medians with plantings
- 4. Traffic control and pavement replacement to install City water distribution and sanitary sewer system infrastructure
- 5. Installation of a water quality treatment system at the Barlow Street intersection, improving water quality along the shore of West Bay adjacent to the Senior Center
- 6. Installation of a water quality treatment system at the Rose Street intersection, improving water quality along the shore of West Bay adjacent to the Rose Street right of way
- 7. Increased storage for the storm water system

SUCCESSES - PROJECT


As a direct result of our commitment to design together, the following examples of design successes that directly relate to the mutual **intent to slow traffic** and improve infrastructure for all users include:


- 1. Front Street and Grandview Parkway intersection design
- 2. Design variance for narrowed travel lanes on NHS route (potentially first ever approved in Michigan)
- 3. Project is designed in such a way as to not preclude any potential future trail expansion or lighting projects
- 4. All pedestrian/trail crossings of Grandview Parkway will be 12' wide along with:
 - a) New pedestrian island and marked crossing near Rose/Peninsula
 - b) Underground conduit for potential future PHB at Rose/Peninsula, Hope, and Oak
 - c) Audible pedestrian signals at Division, Union, and East Front Street

5-2-22 CITY COMMISSION FEEDBACK


- Design Exception Lane Width
 - MDOT reports that the design exception for this project is to be approved at the region level and all indications are that this will be approved
- Curb to Curb map
- Radius of WB Grandview Parkway at Front Street
- HAWK Installation Cost
 - Estimated \$60-100K
- Garfield Intersection
- Division Total Crossing Distance
- Stormwater Maps

CURB TO CURB MAP





Radius of WB Grandview Parkway at Front Street





10

TOTAL PROJECT PAVEMENT IMPACTS

Paved travel way increase: 19,210 sft

• Paved travel way decrease: 30,210 sft

• Total decrease: 11,000 sft

E Front Street and Garfield Intersection








DIVISION TOTAL CROSSING DISTANCE

- Existing 120':
 - Division approximately 50'
 - Grandview Parkway
 - East Leg 70'
 - West Leg no crossing
- Proposed 161':
 - Division 77'
 - Grandview Parkway 84'
 - East Leg no crossing
 - West Leg eastbound (40'), median (18'), westbound (26')

WATER QUALITY
TREATMENT
SYSTEM AT
BARLOW
STREET SERVES:



WATER QUALITY TREATMENT SYSTEM AT ROSE STREET SERVES:



WHAT'S NEXT?

- Scheduling
 - Phasing
 - Coordination with local bridge construction
 - Special Events coordination
- Permitting and Agreements
 - Consent to Grade
 - Detour Routes
 - Traffic Control Plan
 - Cost Share

- Where are we in the process?
 - Final MDOT plan submittal is pending, November letting
- What comes next?
 - Future opportunities
 - TART Trail expansion
 - Lighting improvements
 - Coordination on other projects in the MDOT 5-year capital plan

SCHEDULE

- Project is targeting a November 2022 Bid Letting
- Parkway Construction will not be concurrent with 2023 Traverse City bridge projects
- Prep and some utility work to be completed after Labor Day 2023
- Full construction to occur the entire construction season of 2024 (March-November)
- Final restoration in spring of 2025



CONSEQUENCES OF A YES VOTE

- Reconstructed road per design in 2024
- Safety benefits of design realized sooner
- Major traffic impacts during construction
 - Local detours due to city requested utility work
- City cost participation
- Improved relations with MDOT

CONSEQUENCES OF A NO VOTE

- Grandview Parkway and East Front Street do not get reconstructed until 2029 at the earliest
- Pavement preservation project likely to be programmed instead
- \$19M investment spread to other projects in the region
- Damaged partnership with MDOT

Thank you,

Chris Zull

ZULLC@PROGRESSIVEAE.COM

progressive

